

Standing Walls, Day 1

Overview: Task requires two groups of 6-8 people working together:

- a ground crew to move wall panels from stack to house slab.
- a slab crew to stand the wall panels on the foundation.

Safety Tips: *Work as a team; lift together*
Have a plan; know the direction you are going before lifting panels
Keep area clear around panel stacks and on path to slab foundation
Do not move panels until the slab crew is ready
Do not lean wall panels against other panels
Keep work area on slab clear

Tools: Please see next section "Fastening Walls" for specific tools

Materials: Please see next section "Fastening Walls" for specific materials

