

Stringing and Bracing Walls, Day 1

Overview: Stringing and bracing of the exterior walls can begin as each side is complete and all connecting interior walls are attached to the exterior

The task usually requires 5-6 people working as a team to accomplish

Safety Tips: Make sure all walls are securely and permanently attached to slab and each other before bracing

Exercise ladder safety

Tools:

1 each

6 or 8 foot stepladder

String line

Hammers

Remington gun and loads/nails as necessary

Materials:

2x4x12 foot lumber

2x4 Blocks

16 penny nails

